Supply on our order will be subject to the general conditions of contract prevailing in this department for local purchases.

The tenders should be superscribed "Tender for the supply of 'Porous Pots No. 1 and 2 and rods' to be opened on 21st August 1953.

1.	Porous pots No. 1 best make (complete set)	... 250 sets.
2.	Do No. 2 do	... 250 sets.
3.	Spare Zinc Rods No. 1 for item No. 1 above	... 250 Nos.
4.	Do No. 2 for item No. 2 above	... 250 Nos.

572

Notification dated 20th July 1953.

No. G.N. 38. Sealed tenders will be received in the Office of the Chief Electrical Engineer to the Government of Mysore, Bangalore, up to 3 P.M. on Friday, the 14th August 1953, for the supply and erection of zinc sheet sheds for housing irrigation pump sets in the Mysore State. The tenders should be submitted in duplicate.

Locations.—The sheds have to be erected in different villages of the several districts spread over the entire State. At certain localities the sheds will be rather concentrated according to the installations of the irrigation pump sets. The probable number of sheds to be erected in each district has however been noted in the statement below:—

Sl. No.	Name of the district	Probable number of sheds to be erected in each district.
1.	Bangalore	50
2.	Mysore	50
3.	Mandya	20
4.	Kolar	150
5.	Tumkur	400
6.	Hassan	30
7.	Chikmagalur	60
8.	Chitaldrug	650
9.	Shimoga	350
		1,760

Terms of Quotation:—The tenderers should quote the rate at Rs.....per shed complete erected in all respects. It should include all the required materials such as angle iron, corrugated zinc sheets, zinc bolts and nuts, cement for cement concreting the foundations for the up rights and for the flooring, etc., and also labour charges for preparing the steel frame work and completely erecting the shed in all respects. Since the sheds are required all over the State, the quotations should be based on the lumpsum figure per shed erected completely in any village in the particular district. The number of sheds that the tenderer is willing to undertake in each District should also be furnished. This is essential for the sake of uniformity in the quotation and to facilitate the comparative studies of the same. Completion and delivery period per shed should also be stated. The tenderer may also quote a uniform rate for all the sheds in the State.

Specifications:—Zinc Sheet shed 7'—6"×7'—6"×7½' average height should be constructed as per layout shown in the instruction sheet No. G-975. It should be built of M. S. Angles frame work. The side walls as well as the roof should be covered by 22 Gauge G. I. corrugated sheets of adequate size with sufficient lap of not less than three corrugations and fitted to the frame work by means of 'J' or square bolts as the case may be, and door built of angle iron frame work covered with zinc sheet should be provided with all the necessary hinges and hasps etc., for locking the same. Necessary cement concrete foundations 1:4:8 proportion for the uprights should also be provided as shown in the drawing. The flooring should consist of 3" thick 1:4:8 cement concrete with ½" thick cement mortar plastering of 1:3 proportion.

While laying the floor 3" thick, the space required for the foundation of the pumping unit should be excluded. The size of this should be obtained from the Engineer-in-Charge. This reduction should be taken into consideration while furnishing the quotations.

Necessary holes should be provided in the zinc sheet side walls for the suction and delivery pipes of the pumping unit. The shed in general should conform to the detailed dimensions and specifications furnished in the instruction sheet referred to above.

List of materials and details for erection:—Please *vide* Instruction Sheet referred to above.

Departmental Issues:—The necessary structurals as well as the zinc sheets and bolts and nuts, cement, etc., will be supplied by the Electrical Department to the extent available and the cost of such materials supplied together with 15 per cent incidental charges will be recovered from the bills of the successful tenderer undertaking the work.

Earnest money.—A sum of Rs. 50 in cash for each shed should be deposited by the tendererer along with the tender. The disposal of this earnest money will be regulated as per the existing codal rules of the department.

Last date:—The last date for the receipt of tenders is 14th August 1953.

Period of construction:—The sheds should be constructed and handed over to the Department within one month from the date of order.

General:—(1) The contractor should make his own arrangements for transport of materials, water supply, etc.

(2) Sales-tax, royalty, etc., will have to be paid by the contractor.

(3) Withdrawal from the quotation after it is accepted or failure to construct the sheds within the specified time or according to specifications will entail concellation of the order. Besides, the work will be got executed at the expense of the tenderer from other sources in addition to the levy of a penalty of 5 per cent of the value of the shed. In such an event, the Chief Electrical Engineer will reserve the right to remove the name of the contractor from the list of approved firms, under advice to the Secretary, Stores Purchase Committee, Bangalore.

(4) The successful tenderer while erecting the sheds should strictly follow the instructions that would be given by the Supervising and the Inspecting Officers of the Department and in the event of any dispute the decision of the Chief Electrical Engineer will be final and binding on all the parties.

(5) The intending tenderers should obtain the specifications, instruction sheets, drawings, etc., from this office on payment of Rs. 2 which will not be returned.

N. D. M. APPA,
357 For *Chief Elecl. Engr.*

OFFICE OF THE SUPERINTENDENT, POWER AND LIGHTING, CITY AREA, BANGALORE.

Tender Notification dated 18th July 1953.

Sealed tenders in triplicate for the work mentioned below will be received at the Office of the Superintendent, Bangalore Power and Lighting, City Area, Bangalore, up to 3-30 P.M. on 5th August 1953:—

"Providing Fluorescent Fittings in the Public Branch Records Room at Mysore Government Insurance Department, Bangalore."

Details of specification can be had at the Office of the Superintendent, Bangalore Power and Lighting, City Area, Bangalore.

The earnest money to accompany the tender is Rs. 33 and a further sum of Rs. 33 only will have to be deposited before award of contract.

571

Tender Notification dated 18th July 1953.

Sealed tenders in triplicate for the work mentioned below will be received at the Office of the Superintendent, Bangalore Power and Lighting, City Area, Bangalore, up to 3-30 P.M. on 10th August 1953.

"Providing Heating and Lighting points to the extended portion of the Public Health Institute, Seshadri Road, Bangalore."

Details of specification can be had at the Office of the Superintendent, Bangalore Power and Lighting, City Area, Bangalore.

The earnest money to accompany the tender is Rs. 385 and a further sum of Rs. 385 only will have to be deposited before award of contract.

570 B. M. SAFIULLA, *Supdt.*